



Fact Sheet

Fullerton Road Grade Separation Project

City of Industry and Los Angeles County



Aerial rendering of completed grade separation. View looking south on Fullerton Road.

Project Description

The Fullerton Road Grade Separation Project will lower Fullerton Road under the existing Union Pacific railroad tracks in the City of Industry and unincorporated area of Los Angeles County, between Rowland Street and State Route 60 (SR-60). Plans call for constructing a six-lane roadway underpass on Fullerton Road, four-track railroad bridge and bridge for Railroad Street spanning Fullerton Road. Gale Avenue would be lowered at the intersection with Fullerton Road.

Project Status

The construction contract was awarded in March 2016. Major construction activities began in June 2019 with the closure of Fullerton Road between Gale Avenue and Rowland Street/San Jose for underpass and bridge construction. Roadway widening on Fullerton Road near SR-60 has been completed. The lowering of Gale Avenue is completed, with all east and west lanes open for travel. The project cost is estimated at \$271 million. The project estimated completion date is March 2026.

Project Impacts

The project would reduce an estimated 50.4 vehicle-hours of delay each day at the crossing which is traversed by 49 trains per day, projected to increase to 91 trains by 2025. Fullerton Road carries 23,716 vehicles per day which is projected to increase to 25,315 vehicles by 2025. The project would eliminate delays for emergency responders and crossing collisions. The project would also reduce emissions and eliminate locomotive horn and crossing bell noise. The Federal Railroad Administration has recorded 2 train-vehicle collisions at the crossing in a recent 10 year period.

Project information

For more project information, please call the Project Helpline at (888) ACE-1426 or visit the project website at www.theaceproject.org.